

本管更生工数量表

路線	人孔番号	管径 (mm)	既設 管厚 (mm)	管種	人孔 種別	管路延長 (m)		人孔扣除 (m)	地盤高	管底高		管渠深さ		更生管土被り		設計 土被り	設計 荷重	更生延長 (m)		副管 数量	取付管 数量	施工前処理					施工条件	備考	
						内訳				MH上	MH下	MH上	MH下	MH上	MH下			内訳				突出	モルタル	油脂	段入水	木根			
						補助	単費											補助	単費										
182	182 - 5	250	28	HP	1号			0.45	589.077		587.657		1.42		1.14	1.50	T-25	28.8				7		7/4			夜間施工	1	施工
	1号				29.71		0.45	589.136		587.576		1.56		1.28															
182	182 - 6	250	28	HP	1号			0.45	589.136		587.671		1.47		1.19	1.50	T-25	27.2				7	1	6/4			夜間施工	1	施工
	1号				28.19		0.45	589.156		587.416		1.74		1.46															
182	182 - 7	250	28	HP	1号			0.45	589.156		587.406		1.75		1.47	2.00	T-25	29.0				7		6/4			夜間施工	1	施工
	1号				29.97		0.45	589.060		587.150		1.91		1.63															
182	182 - 9	250	28	HP	1号			0.45	589.060		587.135		1.92		1.64	2.00	T-25	27.1				5		6/4			夜間施工	1	施工
	1号				28.00		0.45	588.774		586.909		1.87		1.59															
197	197 - 2	250	28	HP	小60			0.30	589.094		587.744		1.35		1.07	1.50	T-14	18.4									夜間施工	1	施工
	1号				19.20		0.45	589.474		587.714		1.76		1.48															
197	197 - 3	250	28	HP	1号			0.45	589.474		587.674		1.80		1.52	2.00	T-14	9.4				2	1				夜間施工	1	施工
	1号				10.39		0.45	589.514		587.664		1.85		1.57															
198	198 - 1	250	28	HP	1号			0.45	589.514		587.634		1.88		1.60	2.00	T-14	44.0				3	1	2/4			夜間施工	1	施工
	1号				44.93		0.45	589.124		587.224		1.90		1.62															
198	198 - 2	250	28	HP	1号			0.45	589.124		587.194		1.93		1.65	2.00	T-14	27.1				2	1				夜間施工	1	施工
	1号				28.02		0.45	588.692		586.902		1.79		1.51															
199	199 - 1	250	28	HP	1号			0.45	588.692		586.862		1.83		1.55	2.00	T-14	4.4									夜間施工	1	施工
	1号				5.33		0.45	588.469		586.779		1.69		1.41															
198	198 - 1	300	30	HP	1号			0.45	588.441		587.031		1.41		1.08	1.50	T-14	26.0				8	1	4/4			夜間施工	1	施工
	1号				26.92		0.45	588.204		586.754		1.45		1.12															
198	198 - 2	250	28	HP	1号			0.45	588.204		586.749		1.45		1.20	2.00	T-14	19.9				1	3	3/4			夜間施工	1	施工
	1号				20.85		0.45	587.970		585.805		2.17		1.92															
261	261 - 1	250	28	HP	1号			0.45	585.365		584.235		1.13		0.88	1.50	T-14	27.2				2	3				夜間施工	1	施工
	1号				28.15		0.45	585.326		583.956		1.37		1.12															
261	261 - 2	250	28	HP	1号			0.45	585.326		583.936		1.39		1.14	1.50	T-14	19.5									夜間施工	1	施工
	1号				20.45		0.45	585.119		583.709		1.41		1.16															
261	261 - 3	250	28	HP	1号			0.45	585.119		583.689		1.43		1.18	1.50	T-14	25.0									夜間施工	1	施工
	特殊				26.50		1.05	585.129		583.389		1.74		1.49															
224	224 - 1	300	30	HP	1号			0.45	585.399		584.399		1.00		0.70	1.00	T-14	5.9											調査
	1号				6.80		0.45	585.339		584.299		1.04		0.74															
224	224 - 2	300	30	HP	1号			0.45	585.339		584.209		1.13		0.80	2.00	T-14	17.9				2							調査
	1号				18.85		0.45	585.293		583.413		1.88		1.55															
-	-																												
-	-																												
-	-																												

	管路延長		スパン数	更生延長	施工回数
	補助	単費			
管径 250	319.69	0.00	13	307.00	13
管径 300	52.57	0.00	3	26.00	1
管径 400	0.00	0.00	0	0.00	
管径 500	0.00	0.00	0	0.00	
管径	0.00	0.00	0	0.00	
	0.00	0.00	0.00	0.00	0
合計	372.26	0.00	16.00	333.00	14

	更生延長		削孔数	削孔数	施工前処理数				
	補助	単費			突出	モルタル	油脂	段入水	木根
昼間施工	0.00	0.00	0	0	0	1	0	0	0
夜間施工	333.00	0.00	1	48	13	6	0	0	0
合計	333.00	0.00	1	48	13	7	0	0	0