

本管更生工 数量表																				当初														
路線	人孔番号	管径 (mm)	既設 管厚 (mm)	管種	人孔 種類	管路延長		人孔 控除 (m)	地盤高 (m)	管底高 (m)	管底深さ (m)	更生管 土被り (m)	設計 土被り (m)	設計 荷重	管路延長		副管 数量	取付 数量	施工前処理				道路 幅員	施工 条件	特記									
						(m)	内訳(計上)								(m)	(m)			(m)	(m)	(m)	(m)				(m)	(m)	(m)	(m)	突出	モル タル	油脂	木根	
							補助																											単独
11	11 - 2	250	28	HP	1号	29.88		29.88	0.45	596.143	594.653	1.49	1.24	1.50	T-14	28.98	28.9	1	1						夜間									
	1号				0.45				596.103	594.533	1.57	1.32																						
11	11 - 3	250	28	HP	1号	10.64		10.64	0.45	596.103	594.463	1.64	1.39	1.50	T-25	9.74	9.7							夜間										
	1号				0.45				595.941	594.441	1.50	1.25																						
12	12 - 1	450	38	HP	1号	55.25	55.25		0.45	595.941	594.343	1.60	1.15	1.50	T-25	54.35	54.3	2	1						夜間									
	1号				0.45				595.993	594.149	1.84	1.39																						
	-																																	
14	14 - 1	700	58	HP	1号	36.41	36.41		0.45	590.170	588.045	2.13	1.43	2.00	T-25	34.76	34.7	7	1						夜間									
	1号				1.20				590.132	587.832	2.30	1.60																						
31	31 - 1	400	35	HP	1号	49.81	49.81		0.45	593.699	592.174	1.52	1.12	1.50	T-25	48.91	48.9	4							夜間									
	1号				0.45				593.398	591.830	1.57	1.17																						
34	34 - 1	400	35	HP	1号	2.94	2.94		0.45	593.398	591.828	1.57	1.17	1.50	T-25	2.04	2.0							夜間										
	1号				0.45				593.415	591.780	1.63	1.23																						
35	35 - 1	500	42	HP	1号	17.11	17.11		0.45	593.415	591.752	1.66	1.16	1.50	T-25	16.21	16.2							夜間										
	1号				0.45				593.139	591.564	1.58	1.08																						
35	35 - 2	500	42	HP	1号	29.78	29.78		0.45	593.139	591.553	1.59	1.09	1.50	T-14	28.88	28.8	1	1						昼間									
	1号				0.45				592.531	591.172	1.36	0.86																						
35	35 - 3	500	42	HP	1号	34.92	34.92		0.45	592.531	591.141	1.39	0.89	1.00	T-14	34.02	34.0	2	2						昼間									
	1号				0.45				592.199	590.727	1.47	0.97																						
35	35 - 4	500	42	HP	1号	36.00	36.00		0.45	592.199	590.700	1.50	1.00	1.50	T-14	35.10	35.1	5	2						昼間									
	1号				0.45				591.844	590.294	1.55	1.05																						
35	35 - 5	500	42	HP	1号	22.88	22.88		0.45	591.844	590.284	1.56	1.06	1.50	T-14	21.98	21.9							昼間										
	1号				0.45				591.517	589.967	1.55	1.05																						
35	35 - 6	500	42	HP	1号	10.01	10.01		0.45	591.517	589.877	1.64	1.14	1.50	T-14	9.11	9.1	1						昼間										
	1号				0.45				591.252	589.682	1.57	1.07																						
35	35 - 7	500	42	HP	1号	15.27	15.27		0.45	591.252	589.647	1.60	1.10	1.50	T-14	14.37	14.3	3						昼間										
	1号				0.45				591.053	589.478	1.58	1.08																						
35	35 - 8	500	42	HP	1号	17.63	17.63		0.45	591.053	589.448	1.61	1.11	1.50	T-14	16.73	16.7	2	1						昼間									
	1号				0.45				590.848	589.228	1.62	1.12																						
35	35 - 9	500	42	HP	1号	10.54	10.54		0.45	590.848	589.218	1.63	1.13	1.50	T-14	9.64	9.6	1	1						昼間									
	1号				0.45				590.696	589.141	1.56	1.06																						
35	35 - 10	500	42	HP	1号	7.95	7.95		0.45	590.696	589.136	1.56	1.06	1.50	T-14	7.05	7.0	1	1						昼間									
	1号				0.45				590.644	589.064	1.58	1.08																						
35	35 - 11	500	42	HP	1号	12.34	12.34		0.45	590.644	589.049	1.60	1.10	1.50	T-14	11.44	11.4	2	1						昼間									
	1号				0.45				590.441	588.911	1.53	1.03																						
35	35 - 12	500	42	HP	1号	19.19	19.19		0.45	590.441	588.901	1.54	1.04	1.50	T-14	18.29	18.2	1	1						昼間									
	1号				0.45				590.235	588.635	1.60	1.10																						
35	35 - 13	500	42	HP	1号	4.72	4.72		0.45	590.235	588.185	2.05	1.55	2.50	T-14	3.8	3.8							昼間										
	1号				0.45				590.177	587.450	2.73	2.23																						
						管路延長		スパン 数	管渠 延長	更生延長						削孔 数	削孔 数	施工前処理数																
						補助	単独			補助	単独	屋間 施工		夜間 施工				合計		補助	単独		突出	モルタル	油脂	木根								
		管径 250		40.52		40.5		2		38.72		210.43		164.5		45.4		19		10														
		管径 400		52.75		52.8		2		50.95		194.99		139.9		54.8		14		3														
		管径 450		55.25		55.3		1		54.35																								
		管径 500		238.34		173.0		65.4		13		226.64																						
		管径 700		36.41		36.4		1		34.76																								
		合計		423.27		317.4		105.9		19		405.42		304.4		100.2		33		13														