

《 路線調書 》

当初

路線	人孔番号	管径 (mm)	既設 管厚 (mm)	管種	人孔 種類	管 路 延 長 (m)	管 渠 延 長 (m)	地盤高 (m)	管底高 (m)	深 さ (m)	土被り (m)	設 計 土被り (m)	設 計 荷 重	水 深 (cm)	流 速 (m/s)	製 管 延 長 (m)	管 口 処 理	取 付 管 数	施 工 前 処 理			施 工 時 間 帯	備 考	
																			突 出	木 根	止 水			
5-1	5 - 1	1200	95	HP	特殊	15.25	13.75	591.110	587.930	3.18	1.89	2.00	T-25	15~30	0.6~1.3	13.9	2	1	0	0	6	昼 間		
	特殊				590.900			587.840	3.06	1.77														
5-2	5 - 2	1200	95	HP	特殊	36.81	35.31	590.900	587.770	3.13	1.84	2.00	T-25	15~30	0.6~1.3	35.5	2	0	0	0	6	昼 間		
	特殊				590.600			587.810	2.79	1.50														
6	6 - 1	1200	95	HP	特殊	10.04	8.54	590.600	587.780	2.82	1.53	2.00	T-25	15~30	0.6~1.3	8.7	2	0	0	0	12	昼 間		
	特殊				590.520			587.720	2.80	1.51														
7	7 - 1	1200	95	HP	特殊	23.80	22.30	590.520	587.680	2.84	1.55	2.00	T-25	15~30	0.6~1.3	22.5	2	3	0	0	12	昼 間		
	特殊				590.150			587.420	2.73	1.44														
					管径別集計	管路 延長	管渠 延長	製管 延長	スパン						施工帯別集計	製管 延長	管口 処理	削孔数	施 工 前 処 理 数					
					管径 1200	85.90	79.90	80.6	4						昼 間	80.6	8	4	0	0	36			
					管径	0.00	0.00	0.0	0						夜 間	0.0	0	0	0	0	0			
					管径	0.00	0.00	0.0	0						昼 夜 間	0.0	0	0	0	0	0			
					合 計	85.9	79.9	80.6	4						合 計	80.6	8	4	0	0	36			